830

SHIMOGA DIVISION.

Notice dated 10th November 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 1st December 1928, for restoring Yelavalli Hosakere Registered No. 78, Major Tank, Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 370 in Cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Yelavall Hosakere Registered No. 78 (Major) Sorab Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Yalavalli Hosakere Tank Registered No. 78 of Sorab Taluk.

No.	Items of work	Per	Quantity
	Bund to R. L. 55·00.		
1	Jungle clearing and removing roots, etc., complete ...	L. S.	...
2	Earth work to bund including watering and tamping complete.	C.yd.	8,900
3	Turfing the slopes (both sides)	Sqr.	1021·59
4	Grade stones with bed slabs including cutting figures, painting and fixing complete.	Each	22
5	Index stones opposite to grade stones	,,	22
6	Register No. and date stone including cutting figures, painting and fixing complete.	,,	1
7	Gauge stone with bed slab including chiseling figures, painting and fixing.	,,	1
8	B. M. stones with bed slab including chiseling figures, painting and fixing.	,,	2
	Sluice No. 1 Cill at R. L. 46·00.		
1(a)	Earthwork cut opening the bund	C.yd.	55
(b)	Earthwork refilling with consolidation as above ...	,,	55
(c)	Earthwork excavating foundations	,,	12
2	Stone jelly concrete in surki mortar	C.ft.	291
3	Burnt brick in surki mortar	,,	
	or		233
	Burnt stone in surki mortar	,,	233
4	Burnt stone slabs 6" thick dressed and fixed	S.ft.	113
5	Surki plastering	Sqr.	3·18
6	Cement pointing to burnt stone slab flooring	,,	·55
7	Cutting holes in upper and lower orifice slabs and guide slab.	Lump	sum

No.	Items of work	Per	Quantity
8	Providing cast iron pipes 9" dia including cost Railway freight, cart hire and fixing in cement.	R.ft.	36
9	Providing wooden plugs and 1¼" dia iron rod and locking arrangement complete.	L. S.	...
10	New rough stone work with jelly backing	C.yd.	12
	Sluice No. 2 Cill at R. L. 39·50.		
1(a)	Earthwork cut opening the bund	C.yd.	161
(b)	Earthwork refilling with watering and consolidation ...	„	161
(c)	Earthwork excavating foundation	„	26
2	Stone jelly concrete in surki mortar	C.ft.	625
3	Burnt brick in surki mortar	„	1,013
	or		
	Burnt stone in surki mortar	„	1,013
4	Burnt stone slabs 6" thick dressed and fixed	Sq. ft.	194
5	Surki plastering	Sqr.	11·90
6	Cement pointing to burnt stone slab flooring	„	1·34
7	Cutting holes in upper and lower and guide, orifice stones...	L. S.	...
8	Providing cast iron pipes of 9" dia including cost, Railway freight and cart hire and fixing in cement.	R.ft.	36
9	Providing wooden plugs and 1¼" iron rod and locking arrangement complete.	L. S.	...
10	New rough stone work with jelly backing	C.yd.	15
	Waste Weir at R. L. 50·00.		
1	Earthwork excavation for foundation	C.yd.	31
2	Stone jelly concrete in Surki mortar	C.ft.	81
3	Burnt brick in surki mortar	„	179
	or		
	Burnt stone in surki mortar	„	179
4	Burnt stone slabs 6" thick dressed and fixed	Sq. ft.	66
5	Plastering with surki mortar	Sqr.	2·18
6	Rough stone work new including jelly backing ..	C.yd.	44

M. A. SRINIVASACHARI,
Executive Engineer.

CHITALDRUG DIVISION.

No. 396, *dated 5th November* 1928.

"The attention of the public is hereby invited to the advertisement on P. P. 1183 and 1184 of Part VI of the *Mysore Gazette*, dated 1st November 1928. calling for tenders for improving Bhattarahalli Tank Feeder Channel in Molakalmuru Taluk. The date of receipt of tenders which was fixed as 5th November 1928 has been extended up to 2 P.M., on 26th November 1928."

Abstract Notification dated 31st October 1928.

The attention of the public is hereby invited to the advertisement page Nos. 1319-1320 of the *Mysore Gazette* of 8th November 1928, calling for tenders for the work of Constructing Mutton Stalls at Davangere Town, Davangere Taluk.

A. TANDONI RAO,
Executive Engineer.

MYSORE SPECIAL DIVISION.

Abstract Notification.

The attention of the public is invited to the notification published on pages 1350 and 1351, Part VI of the *Mysore Gazette*, dated 15th November 1928, calling for tenders for the extension of the Nanjaraja Bahaddur Chattram, Mysore. The last date of receipt of tenders is 8th December 1928.

V. V. KARVE,
Executive Engineer.